




OIL SPILL RESPONSE SERVICES in PERU 2014 – 2016 Projects





**OIL SPILL RESPONSE
SERVICES
in PERU**

2014


PETROPERÚ PIPELINE – KM 41

2016

- PETROPERÚ PIPELINE – KM 440
- PETROPERÚ PIPELINE – KM 67
- PETROPERÚ PIPELINE – KM 55&54
- PETROPERÚ PIPELINE – KM 53
- PETROPERÚ PIPELINE – KM 364
- PETROPERÚ PIPELINE – KM 206
- PETROPERÚ PIPELINE – KM 213
- PETROPERÚ PIPELINE – KM 103

Finalized

**In
progress**



Based on:

American Petroleum Institute (API): Report on options to minimize environmental impact in response to land spills.

International Petroleum Industry Environmental Conservation Association (IPIECA): Development of response strategies using the Net Environmental Benefit Analysis – NEBA.

Federal Remediation Technologies Roundtable (FRTR) remediation technology matrix.

CONTAIMENT



OIL RECOVERY



TEMPORARY STORAGE



SPECIALIZED CLEANING



WASTE MANAGEMENT



EXPERIENCES

BEFORE



AFTER



PETROPERU PIPELINE KM 41

Year 2014. Spilled volume: 2.000 Bbls
Time of work: 119 days
Remediated area: 86,500m²
Status: finalized

LAMOR technicians: 35

Local personnel: 400

Specialized equipment: LAMOR skimmers, solid pumps, hot washers, booms

BEFORE



AFTER



PETROPERU PIPELINE KM 440

Year 2016. Spilled volume: 4.000 Bbls
Time of work: 112 days
Remediated area: 32,500m²
Status: finalized

LAMOR technicians: 15

Local personnel: 400

Specialized equipment: LAMOR skimmers, solid pumps, hot washers, booms

BEFORE



AFTER



PETROPERU PIPELINE KM 364

Year 2016. Spilled volume: 52000 Gal
Time of work: 40 days
Remediated area: 12.000m²
Status: finalized

LAMOR technicians: 16


Local personnel: 155 approx.

Specialized equipment: LAMOR skimmers, solid pumps, hot washers, booms

BEFORE



AFTER



PETROPERU PIPELINE KM 54 & 55

Year 2016.

Time of work: 98 days

Remediated area: 41.000m²

Status: finalized

LAMOR technicians: 16

Local personnel: 300 approx.

Specialized equipment: LAMOR skimmers, solid pumps, hot washers, booms

BEFORE



AFTER



PETROPERU PIPELINE KM 53

Year 2016.

Time of work: 45 days

Remediated area: 32.000m²

Status: finalized

LAMOR technicians: 15

Local personnel: 85.

Specialized equipment: LAMOR skimmers, solid pumps, hot washers, booms

BEFORE



AFTER



PETROPERU PIPELINE KM 82

Year 2016.

Time of work: 45 days

Remediated area: 5.500m²

Status: finalized

LAMOR technicians: 14

Local personnel: 120

Specialized equipment: LAMOR skimmers, solid pumps, hot washers, booms

BEFORE



AFTER



PETROPERU PIPELINE KM 67

Year 2016.
Time of work: 70 days
Remediated area: 9.100m²
Status: finalized

LAMOR technicians: 24

Local personnel: 136

Specialized equipment: LAMOR skimmers, solid pumps, hot washers, booms

BEFORE



AFTER



PETROPERU PIPELINE KM 206

Year 2016. Spilled volume: 2.000 Bbls
Time of work: 426 days
Remediated area: 1'240.000m²
Status: in progress

LAMOR technicians: 45

Local personnel: 2000 approx.

Specialized equipment: LAMOR skimmers, solid pumps, hot washers, booms

BEFORE



AFTER



PETROPERU PIPELINE KM 213

Year 2016. Spilled volume: 903 Bbls

Time of work: 260 days

Remediated area: 30.000m²

Status: *in progress*

LAMOR technicians: 16

Local personnel: 155 approx.

Specialized equipment: LAMOR skimmers, solid pumps, hot washers, booms

BEFORE



AFTER



PETROPERU PIPELINE KM 103

Year 2016. Spilled volume: N/D Bbls

Time of work: 165 days

Remediated area: 240.000m²

Status: in progress

LAMOR technicians: 22

Local personnel: 410

Specialized equipment: LAMOR skimmers, solid pumps, hot washers, booms



A Polyeco Group Company



polyecogroup
EST. 1977

REPSOL Km 66 pipeline: *in situ* remediation project


REPSOL





BACKGROUND:

- In August 2014 REPSOL ECUADOR identified a diesel spill in the km66 of their pipeline inside Block 16.
- In march 2015, TEMALISA developed the delimitation of the affected area.
- In July 2016, CORENA and TEMALISA began the remediation activities of the affected area.



REF.: 1103_8050

PLANO Nº: 01

FECHA: Diciembre 2015

ESCALA: S/E

REMEDIACIÓN DEL SUBSUELO DE LA ZONA DE DERRAME DEL KM66, BLOQUE 16

SITUACIÓN GEOGRÁFICA




REALIZADO: D. Matas

REVISIÓN: 0




SOIL CONTAMINATION BASE LINE

*Highest
contamination:
13.000 mg/Kg*




WATER CONTAMINATION BASE LINE

*Highest
contamination:
1.370 mg/mL*



CROSS-SECTION




SCOPE OF WORK:


- Recovery of the non-aqueous free phase (diesel) from the affected area.
- Remediation of the subsoil, from the pipeline break site, through the hill and to the river at the end of the hill

REMEDIATION METHOD: ELECTROKINETIC ENHANCED BIOREMEDIATION

Electrokinetic reactions (EKO GRID®)




Microbiological augmentation



Supply of O₂





GRID AND TRENCHES DESIGN

LEGEND

- | | |
|--------------------------|-------------------------|
| Pipeline break | Pipeline |
| Permanent sampling point | Road |
| EKO GRID Anode | Trenches |
| EKO GRID Catode | River |
| National Park | Contamination perimeter |

RESULTS MARCH 2017: 2nd month of operation

Water samples results


N°.	Código	Fecha	Resultado	
			TPH (mg/l)	HAP (mg/l)
1	A-PZ-3	01/02/2017	4,80	0,0013
2	A-PZ-6	01/02/2017	7,75	0,0014
3	A-PZ-7	01/02/2017	14,39	<0,0003
4	A-PZ-9	01/02/2017	<0,25	-
5	A-PZ-10	01/02/2017	0,73	-
6	A-PZ-15	01/02/2017	<0,25	

Soil samples results

N°.	Código	Fecha	Resultado		LMP (Tabla 6 RAOHE. Eco. Sensibles)	
			TPH (mg/l)	HAP (mg/l)	TPH (mg/l)	HAP (mg/l)
1	S1-KM66-01	28/01/2017	276,99	-	< 1000	< 1
2	S2-KM66-01	28/01/2017	81,28	< 0,3	< 1000	< 1
3	S3-KM66-01	28/01/2017	447,66	-	< 1000	< 1
4	S4-KM66-01	28/01/2017	< 70	< 0,3	< 1000	< 1
5	S5-KM66-01	28/01/2017	367,88	-	< 1000	< 1
6	S6-KM66-01	28/01/2017	< 70	-	< 1000	< 1
7	S7-KM66-01	28/01/2017	< 70	< 0,3	< 1000	< 1
8	S8-KM66-01	28/01/2017	< 70	< 0,3	< 1000	< 1

Even though first results show values under the accepted limit (soil 1.000 mg/kg) at 3m of depth, the second sampling tasks (at the end of April 2017) will cover a depth between 3 and 5m to evaluate the behavior of the system. Regarding to water, the target limit is not achieved yet (<20 mg/L), which shows that the remediation process should continue. A 12-month remediation period is estimated.






SYMBOLS

- Perimeter of contamination
- River
- Pipeline perimeter
- Road
- National Park
- Diesel pipeline
- Oil pipeline
- Optical fiber
- Power cable

LEGEND

- ⊙ Soil sample
- ⊙ Water sample

GRAPHIC SCALE



REPSOL		TEMALISA S.A.
PROYECTO :		TRABAJOS DE REMEDIACION DERRAME KM 66 ID 43664
CONTENIDO :		RESULTADOS DE ANALISIS DE MUESTRAS DE SUELO Y AGUA
Ref: 8250	Realizado por: NC	Fecha: Feb, 2016
Plano: N° 2	Escala: Gráfica	Revisión: 0

